

Building Plan Fire Department Notes

1. Any penetrations through a fire-rated assembly shall be sealed using approved methods and materials. Provide the appropriate UL detail/cut sheets in the plans.
2. All fire-rated assemblies shall be permanently and effectively marked using signs or stencils in the concealed space.
3. All mechanical, electrical, and fire sprinkler riser rooms shall be labeled.
4. Due to the on-site bulk storage of CO₂, a CO₂ alarm/monitoring system will be required to be installed, and NFPA 704 placards will be required to be posted on all entry/exit doors.
5. Due to the size of the building (any building over 12,000 square feet), an emergency responder radio signal test shall be conducted and passed before the issuance of a Certificate of Occupancy.
6. If a kitchen hood fire extinguishing system is to be installed, it is a deferred submittal. Plans shall be submitted to and approved by the Fire Marshal's office before the system is installed.
7. If any modifications are made to the fire alarm or fire sprinkler systems, that requires a deferred submittal, and plans shall be submitted to and approved by the Fire Marshal's office before the modification of these systems.